

Hershey Theatre Line Set Schedule

12/13/2011

SET #	DISTANCE	NOTE 1	NOTE 2
	-8-4	Downstage Edge of Stage	
	-3-4	Upstage Edge of Proscenium	
	-2-5	Upstage Edge of Smoke Pocket	
1	-2-0	House Valance - Lattice Track Stage Left	Cannot be kicked - Sag Bar Support
2	-0-11	Main Drape - Motorized Guillotine & Draw	Cannot be kicked - Sag Bar Support
3	0-0	FIRST SET AVAILABLE TO ROAD SHOW	Cannot be kicked - Sag Bar Support
4	0-8		
5	1-4		
6	2-0		Cannot be kicked - Sag Bar Support
7	2-8	HOUSE MOVIE SCREEN STORAGE	
8	3-4		
9	4-0		
10	4-8		
11	5-4		
12	6-0		Cannot be kicked - Sag Bar Support
	6-8	Grid Support	
	7-4	Load Bridge Support	
13	8-0		Cannot be kicked - Sag Bar Support
14	8-8		
15	9-4		
16	10-0		
17	10-8		Cannot be kicked - Sag Bar Support
	11-4	Sprinkler Obstruction	
18	12-0	Sprinkler Obstruction - Limits Max Out Trim	
19	12-8		
20	13-4		
21	14-0		
22	14-8		Cannot be kicked - Sag Bar Support
23	15-4		Cannot be kicked - Sag Bar Support
24	16-0		
25	16-8		
	17-4	Load Bridge Support / Out Rigger Bracket	
26	18-0		
27	18-8		Cannot be kicked - Sag Bar Support
28	19-4		
29	20-0		
30	20-8		
31	21-4		
32	22-0		
33	22-8		Cannot be kicked - Sag Bar Support
	23-4	Grid Support	
34	24-0		Cannot be kicked - Sag Bar Support
35	24-8		
36	25-4		
37	26-0		Cannot be kicked - Sag Bar Support
38	26-8		Cannot be kicked - Sag Bar Support
39	27-4		
40	28-0		
41	28-8		
42	29-4		
	30-0	Load Bridge Support / Out Rigger Bracket	
43	30-4		Cannot be kicked - Sag Bar Support
44	31-0		
45	31-8		
46	32-4		
47	33-0		
48	33-8		
49	34-4		Cannot be kicked - Sag Bar Support
	38-7	Back Wall	

NOTE: Double Purchase System

NOTE: Sets are on 8" centers typ.

NOTE: Arbor Capacity is 1000lbs. over pipe weight

NOTE: Batten lengthy is 52'-6' (5' extension is available for SL)